Town of Altona Public Water System Annual Report 2017

The Town of Altona 2017 Annual Public Water System Annual Report was placed on the town website (www.altona.ca) on February 9, 2018.

Free paper copies of the report are available at the Town of Altona administration building located on 111 Centre Avenue East.

The public will be notified via the Town's website as well as a poster on the Town's bulletin board in the Town office.

Town of Altona Public Water System Annual Report 2017

Name of the Public Water system: Altona Public Water System Name of the Legal Owner: The Town of Altona Phone: 204.324.6468 Contact person: Dan Gagné (CAO) Email: dan.gagne@altona.ca

Supervisor: Clint Derksen Phone: 204.324.7467 Email: <u>clint.derksen@altona.ca</u> Senior Operator: Aaron Schmidt Phone: 204.324.4657 Email: <u>waterworks@altona.ca</u>

Report Prepared: February 5, 2018

The 2017 Annual Report for the Town of Altona summarizes the Water Utility's ability to distribute safe potable water and meet provincial regulations.

1. Description of the Water System:

The Altona Water System provides potable water to a population of approximately 4,218 residents. Treated water supplied by the Pembina Valley Water Coop meets all objectives as stated in the Guidelines for Canadian Drinking Water Quality.

1.1 Water Supply Source

The Altona Water System receives treated water from Letellier which is 20 kilometres east of Altona. The Letellier plant draws water from the Red River and treats the water before distribution.

1.2 Distribution System

Treated water from the reservoirs is pumped throughout the Altona distribution system via four 15 horsepower duty pumps and two 75 horsepower emergency pumps. The approximate 33 kilometers of piping is 99% looped and is comprised of 59% AC, 40% PVC, and 1% HDPE.

1.3 Storage Reservoirs

Name: North End Reservoir	Capacity: 3 222 000 L
Name: South End Reservoir	Capacity: 1 453 000 L

1.4 Number of Connections, population served and types of users

The Altona distribution system is comprised of 1,375 service connections. All connections are metered. Domestic use is the largest consumer with approximately 65% while commercial use is approximately 35%.

1.5 Classification and Certification

Operators are certified under Manitoba Conservation's Water and Wastewater Facility Operators Regulation under the Environment Act

Clint Derksen- Supervisor Matthew Aaron Schmidt Jackson Enns Chris McNeil Cert # 2014-081 - WD2, WWC2, WWT1 ID # 0008410 – WD2, WWC2, WWT1 ID # 03223 – WD1, WWC2, WWT1 Operator in training

WT-Water Treatment WD-Water Distribution WWT-Waste Water Treatment WWC-Waste Water Collection CC-Conditional Certificate

2. Disinfection system in use

The last step before distribution is the addition of 12% sodium hypochlorite to the water while entering the reservoirs. The dosage is flow-paced to maintain a minimum of 0.5 mg of free chlorine per litre before it enters the distribution system. There is a minimum of 0.1 mg of free chlorine per litre at all times in the distribution system.

2.1 Equipment and monitoring requirements

As required, the Altona PWS insures continuous disinfection is maintained by stocking all spare parts for chlorinators and a complete spare chlorinator is kept at the reservoirs.

Free Available and Total Chlorine residuals are monitored **daily** by staff and on-line chlorine analyzers at the reservoirs and bi-weekly throughout the distribution system. A *Hach* portable colorimeter test kit, which is calibrated annually, is used for the testing at the South reservoir. An Orbeca portable colorimeter test kit, which is also calibrated annually, is used for the testing at the North reservoir. All results are recorded on the appropriate monitoring forms. Bi-weekly samples are sent to ALS labs for testing. In 2017 the Town of Altona was not required to test for THM/HAA. Monthly chlorination reports are sent to the Drinking Water Officer at the end of each month.

Tests performed bi-weekly:

-**Total Coliform:** a measurement of the total coli form present in bi-weekly samples submitted to ALS labs.

-Escherichia coli: a measurement of the Escheria coli present in bi-weekly samples submitted to ALS labs.

Quarterly samples, every other year, are also collected in the distribution system and to the lab for **THM** testing and **HAA** testing.

- **THM** is the abbreviation for Trihalomethane, which is a chlorination/disinfection byproduct.

- **HAA** is the abbreviation for Haleo Acetic Acid, which is a chlorination/disinfection byproduct.

2.2 Overall performance

For 2017, the Altona PWS met all daily and bi-weekly sampling requirements achieving a 100% efficiency rating. The following tables outline the requirements and performance of the PWS in the Town of Altona for 2017 as outlined in the Operating License (see attached 2017 Annual Compliance Audit)

Disinfection Monitoring and Reporting	Regulatory Requirement	PWS Performance
A)Free Chlorine residual entering the distribution system Section 21(1)a – MR 40/2007	≥ 0.5mg/L	100%
B)Frequency of testing entering the distribution system Section A – MR 40/2007	Daily	100%
C)Free Chlorine residual in the distribution system Section 22a – MR 40/2007	≥ 0.1mg/L	100%
D)Frequency of testing in the distribution system Section A – MR 40/2007	Bi-Weekly	100%
E)Report Submissions Section 25(2) – MR 40/2007	Monthly	100%
The PWS has met all regulatory requirements for 2017 in this	s area.	

Bacteriological Monitoring and Reporting	Regulatory Requirement	PWS Performance
A)Number of samples of watering leaving the North End	26	100%
Reservoir		
Schedule A – MR 40/2007		
B) Number of samples of watering leaving the South End	26	100%

Reservoir			
Schedule A – MR 40/2007			
C)Number of distribution water samples Schedule A – MR 40/2007	26	100%	
D)Frequency of Testing	Bi-weekly	100%	
Schedule A – MR 40/2007			
E)Total Coli form present in samples	0 TC per	100%	
Section 3(1)b – MR 40/2007	100ml*		
F)E. Coli present in Samples	0 EC per	100%	
Section3(1)a – MR 41/2007	100ml		
The Public water System has met all regulatory monitoring requirements for 2017. The water			
system was deemed to be in compliance with all terms and conditions in the Operating License.			

Disinfection By-products Monitoring and Reporting – THMs and HAAs

THM and HAA testing will continue in 2018.

Engineering Assessment of Water System Infrastructure and Water Supply Source

As specified by the operating license, The Altona PWS was required to initiate an Engineering Assessment of the Water System Infrastructure and Water Supply Source. JR Cousin Consultants has completed the Town of Altona Public Water System Assessment 2016 PWS 4.00, Two copies of the report were mailed to The Office of Drinking Water.

3. Water System incidents

In 2017 there were no major incidents.

4. Drinking water orders

In 2017 there were no Safety orders issued for Altona Public Water System. (see attached 2017 Annual Compliance Audit)

5. Boil Water Advisories issued and actions taken

In 2017 there were no Boil Water Advisories issued for the Altona Public Water System.

6. Operational Requirements

The Town of Altona is in non-compliance with both THM and HAA requirements issued for the Altona Public Water System. We are working with Pembina Valley Water Corporation to remedy this in the future.

7. Major Waterline Extensions 2017

In 2017 there were no major waterline extensions.

8. Future system expansion

In 2018 the Town of Altona is looking into looping the area in front of W.C. Miller, along 6th st SE.

The "Town of Altona Public Water System 2017 Annual Compliance Audit" performed by the Office of Drinking Water is attached for reference at the end of this report.

Report Prepared by:

Clenter

Clint Derksen Public Works Manager Town of Altona Office: 204.324.6439 Cellular: 204.324.7467 clint.derksen@altona.ca